

David Gee, Sheriff
HILLSBOROUGH COUNTY SHERIFF'S OFFICE
TAMPA, FLORIDA 33601

DATE: January 27, 2017

SUBJECT: Amendment No. 2 to RFP No. 2-17 Sheriff's Operation Center Roof Replacement

MESSAGE: Please note and acknowledge the following changes or additions to be included in the referenced section(s) of RFP No. 2-17:

Reference Part C – Technical Specifications

1. Certain Technical Specifications have been edited in Part C - Technical Specifications, pages 24-25
2. Part C, Paragraph (4)(b) – Replace (b) in its entirety as follows:
 - b. Removal of existing roof to the sloped lightweight insulating concrete and roof accessories to include but not limited to, roof edge flashing, base flashings, counter flashings, cant strips etc., along with removal and reinstallation of roof top equipment or accessories as necessary.
3. Part C, Paragraph (4)(i) – Replace (i) in its entirety as follows:
 - i. The parapet wall is approximately 166 linear feet. The parapet wall cap shall color match the existing cap on the adjacent building, SOC Annex. An elastomeric or equivalent type of waterproof coating shall be applied to the entire parapet wall. Pictures of the parapet wall can be found in Exhibit B.
4. Part C, Paragraph (4) – Letter (k) has been added as follows:
 - k. The roofing contractor shall be responsible for providing and installing, per applicable codes, new HVAC stands for the two (2) existing HVAC condensing units. The stands shall have height and width adjustments to accommodate the condensing units currently in use.
5. Part C, Paragraph (5)(a) – Replace (a) in its entirety as follows:
 - a. PVC Membrane or Thermoplastic Polyolefin Sheet (TPO) Roofing:
 - I. Manufacturers: Carlisle Syn Tec, Duro-Last Roofing, Inc, Flex Roofing Systems, GAF, Commercial Roofing Products, Versico Roofing Systems, Sika Corporation Commercial Roofing Systems, The Garland Company.
 - II. Type: Fully adhered.
 - III. Membrane: PVC, 60 mils minimum as defined by ASTM D4434 Type III, fabric reinforced.

- IV. Walkways: Walkway pad.
- V. Manufacturer's Warranty: Complete, minimum 20 year, edge to edge, no dollar limit, roof guarantee.
- VI. Workmanship warranty shall be extended for a period of no less than two years from Certificate of Completion date.

6. Part C, Replace Paragraph (6) in its entirety as follows:

Installation:

- a. Comply with roof system manufacturer's instructions and recommendations.
- b. Install walkway protection over an additional layer of membrane where required to provide access to roof mounted AC equipment.
- c. Restore or replace damaged components. Protect work from damage.
- d. Replace roof drains, if necessary.
- e. Must meet all federal, state, and local laws, ordinances, and applicable codes.
- f. Use experienced installers

Please note that this document hereby becomes a part of RFP No. 2-17 and without this document the Proposal is considered incomplete.

Sincerely,

- SIGNATURE ON FILE -

Christina R. Porter, CPA
Chief Financial Officer

ACKNOWLEDGEMENT OF AMENDMENT

We do hereby acknowledge the information and/or changes to the Scope of Work described in
Amendment No. 2 to RFP No. 2-17

PLEASE PRINT - Company Name_____

By_____

Title_____

Date_____

*Signature*_____

(Signed Acknowledgement must be included with your RFP/Bid Package)