

Questions & Answers #2

1. Please provide type of glass required for view lites on doors and windows.

Answer: *Glass for Interior Non-Rated Doors, Sidelights, and Windows: 1/4-inch thick clear tempered glass.*

2. Notes 4,5 and 6 are missing on page A-600, remarks on the door schedule refer to those notes, please clarify.

Answer: *Note 4: Existing door, provide new hardware.*

Note 5: Existing door to be locked and sealed. Provide interior wall infill similar to Wall Type S3C.

Note 6: Exterior emergency egress door, exit only.

3. Please identify wall types, per page A-110 some walls are missing labels.

Answer: *Per Note 3 on A-110, all walls are S4A unless noted otherwise. Walls missing labels are S4A.*

4. Please confirm if the lockers, TV, gun lockers and 3x4 storage cubies are part of the contract or if those items will be provided by owner.

Answer: *Contractor furnished and installed.*

5. Per section 102800 Toilet, Bath and Laundry Accessories schedule item SPD is CFCI, please provide location for this accessory.

Answer: *Located on Control Wall, rim of SPD at 42" AFF and middle of SPD 12" off back wall.*

6. Provide specifications for the desired epoxy paint on finish schedule

Answer: *Provide Epoxy System: Eg-Shel Finish*

1) S-W Premium Wall & Wood Primer, B28W8111 (1.8-mil dry) – MPI #N/A

2) S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 / B73V300– MPI #254X-Green

3) S-W Pro Industrial Water Based Catalyzed Epoxy Eg-Shel, B73-360 / B73V300 (2.0- 4.0-mil dry per coat)

7. Is there any AS Built of the existing facility?

Answer: *No*

8. Please provide location for the access panels.

Answer: *Access panels for plumbing access are to be determined in field as required if in concealed walls.*

9. Please confirm if the scope of work described on page T-201 is part of the bid alternate no.1

Answer: *The scope for T-201 is part of Bid alternate 1, but please refer to responsibility matrix on sheet T-001 for details on who provides AV equipment.*